

MADHYA PRADESH POWER TRANSMISSION COMPANY LIMITED

OFFICE OF THE SUPERINTENDING ENGINEER(T&C)

E-mail ID setujin@yahoo.co.in

Enq.NO.SE/T&C/UJN/PUR/ 366

Telepone:- 0734-2530136.

Ujjain,dtd. 24.5.18

To,

Through Company web site

M/s ~~www.mp.gov.in~~
~~www.mp.transco.mic.in~~
~~www.fenderhome.com~~
Notice Board.

Sub:- Enquiry for Dismantalling and Dragging of 40MVA 220/132KV Unit BHEL make X-mer Sr.No. 82 & Sr.No.84 installed at 220KV S/S Ujjain.

###

Dear Sir,

Please quote your lowest rates for the under mentioned job work in a sealed envelope, so as to reach this office on or before 07.06.2018 Upto 3.30 PM and will be opened at 4 PM.Your offer shall be governed with terms and conditions noted below:-

Sr.No.	Short description of material	Approx.Qty.
1.	Dismantalling of 40MVA,220/132KV BHEL make X-mer Sr.No.82 at 220KV S/S Ujjain. The scope of work involves dismantalling of all accessories I.e. Radiator,Conservators,Cooling Fans,Marshalling Box etc. and all the associated pipe lines, after dismantalling all the accessories and other dismantalled items are to be stacked to a distance as per directives of Sub-station Incharge.	1 Job.
2.	Dragging of 40MVA,220/132KV BHEL make X-mer Sr.No. 83 having weight 65MT (Approx) (With oil & bushing) to a distance of 40 Meters including 2 Nos. 90 digree turning as per instruction of EE (Testing) Ujjain at 220KV S/S Ujjain.	1 Job.
3.	Dismantalling of 40MVA,220/132KV BHEL make X-mer Sr.No.84 at 220KV S/S Ujjain. The scope of work involves dismantalling of all accessories I.e. Radiator,Conservators,Cooling Fans,Marshalling Box etc. and all the associated pipe lines, after dismantalling all the accessories and other dismantalled items are to be stacked to a distance as per directives of Sub-station Incharge.	1 Job.
2.	Dragging of 40MVA,220/132KV BHEL make X-mer Sr.No. 84 having weight 65MT (Approx) (With oil & bushing) to a distance of 15 Meters without turning as per instruction of EE (Testing) Ujjain at 220KV S/S Ujjain.	1 Job.


TERMS AND CONDITIONS

1. Please submit Rs. 4000/- only towards Earnest Money in the form of D.D drawn in favour of R.A.O,MPPTCL, Indore, alongwith offer, in absence of which your offer may not be considered.

2. The bidder must have EPF Registration, GST Registration, on the name of firm or individual.
3. He must submit the Income Tax return of last three years and having workmen compensation policy for workers.
4. He should experience of working of dismantling dragging / erection in MPPTCL or other similar organisation.
5. He should submit the list of available T&P for above work.
6. L-1 bidder should have to deposit 10% as Security of order value and to execute agreement with the concerned EE (Testing).
7. T&P & other material and labour required for aforesaid work is to be arranged by the contractor at site.
8. For any loss and damage of material, the contractor shall be sole responsible and MPPTCL shall not bear any responsibility.
9. Payment:- As per practice in vogue, the payment shall be released generally within 45 days after completion of the work.
10. The insurance of working personal should be arranged by the contractor.
11. Enquiry No. and date should be clearly mentioned over quotation.
12. Quotation should be clear and visible and there must not be any overwriting or cutting, otherwise it will be rejected.
13. In case of work is not completed within stipulated time penalty will be imposed as per rule.
14. There will be no any liability of MPPTCL for any mishapping with the contractors labour during the work. All the liability will be borne by contractor.

Thanking you.

Yours faithfully



**SUPERINTENDING ENGINEER(T&C)
M.P.POWER TR.COMP.LTD. UJJAIN**