

M.P. POWER TRANSMISSION COMPANY LTD.**TESTING DIVISION UJJAIN**

Executive Engineer (Testing), MPPTCL, Jyoti Nagar (MPSEB Colony) Opp. GDC Dashehra Maidan
Ujjain-456010 Phone no. 0734-2530141

No.EE/T/UJN/PUR/52/2575

Ujjain dated:- 07.02.2019

To,

www.mp.gov.in

www.mptransco.nic.in

www.tendershome.com

Notice Board

Sub:- Enquiry for Cleaning, Scrubbing & Painting of 3 No. X-mer at 132 KV S/s Mahidpur.

Dear Sir,

Please quote your lowest rates for the under mentioned job work in a sealed envelope, so as to reach this office on or before 01.03.2019 Up to 3.30 PM and will be opened at 4 PM, your offer will be governed with terms and conditions noted below :-

S.N.	Description of job work	Quantity
A.	Painting of Transformer	
1	Providing anticorrosive gray paint on 20 MVA X-mer-I NGEF bearing Sr. no. B-2800036656 work including conservator, piping, bushing, Turrets, Thermosyphone, Radiators, fans, fans frame, Marshalling box, control cubical at 132 KV S/s Mahidpur. Single coat of anticorrosive Smoke gray paint is to be applied. The paint should be of good conductor of heat and of reputed brand i.e.Asian/Berger etc.The paint should be applied by spray machine. The paint is to be provided by contractor scrubbing & cleaning of complete equipments and ensuring that grease/oil has been washed out before painting, also painting of X-mer wheels and Rail (with black paint) under the X-mer should be covered. (Red, Yellow, Blue on bushing and wheel by black paint).	1 NO'S Job Work
2	Providing anticorrosive gray paint on 20 MVA X-mer-II BHEL bearing Sr.no. 6004543 at 132 KV S/s Mahidpur painting work including conservator, piping, bushing, Turrets, Thermosyphone, Radiators, fans, fans frame, Marshalling box, control cubical at 132 KV S/s Mahidpur. Single coat of anticorrosive Smoke gray paint is to be applied. The paint should be of good conductor of heat and of reputed brand i.e.Asian/Berger etc.The paint should be applied by spray machine. The paint is to be provided by contractor scrubbing & cleaning of complete equipments and ensuring that grease/oil has been washed out before painting, also painting of X-mer wheels and Rail (with black paint) under the X-mer should be covered. (Red, Yellow, Blue on bushing and wheel by black paint).	1 NO'S Job Work
3	Providing anticorrosive gray paint on 40 MVA X-mer-III BBL bearing Sr.no. 5033/24 not painting is not done . At 132 KV S/s Mahidpur, painting work including conservator, piping, bushing, Turrets, Thermosyphone, Radiators, fans, fans frame, Marshalling box, control cubical at 132 KV S/s Mahidpur. Single coat of anticorrosive Smoke gray paint is to be applied. The paint should be of good conductor of heat and of reputed brand i.e.Asian/Berger etc.The paint should be applied by spray machine. The paint is to be provided by contractor scrubbing & cleaning of complete equipments and ensuring that grease/oil has been washed out before painting, also painting of X-mer wheels and Rail (with black paint) under the X-mer should be covered. (Red, Yellow, Blue on bushing and wheel by black paint).	1 NO'S Job Work
(The job can be seen at site on any working day during working Hrs.)		

TERMS AND CONDITIONS.

01. T&P, other material and labour required for above work is to be arranged by the contractor at site.

cont.2


02. For any loss and damage of material the contractor shall be sole responsible and MPPTCL shall not bear any responsibility.
03. **Payment :-** 100%payment within reasonable time after completion of aforesaid job work.

The satisfactory completion of the Job work bill in triplicate shall be submitted to the A.E. 132 KV S/s Mahidpur E.E.(T) Ujjain, who will verify and forwarded the same to the R.A.O. MPPTCL Indore for releasing the payment, after deducting Income - Tax as per rules.

04. The insurance of working personal should be arranged by the contractor.
05. **Penalty :-** In case of delay 0.5 %per week & part thereof subject to maximum of 10% from contractor bill.
06. The Enquiry can be cancelled without any liability.
07. **Enquiry No. and date should be clearly superscribed on envelope.**
08. **GST no. & PAN no. should be mentioned on enquiry/enclosed.**
09. After handingover of the site the area of work will be inspected by the site incharge, if not found satisfactory, the penalty will be imposed @1% per week or part thereof.
10. The contractor shall be responsible for any loss of life disability of his works because his carelessness in the proximity of charged EHV S/s. The contractor shall provide a suitable insurance cover to his worker. Any compensation required to be paid on this ground, if any, shall be born by the contractor.
11. It may please be noted that the deployed employee shall not be allowed to do any work other than stipulated in the tender. In case, in unfortunate even if the accident while carrying out unauthorized work, the responsibility for same shall lie on the contractor. In case of any such accident, the contractor shall be liable to compensate the deceased or his family for Rs. 5 lacs in case of body injury resulting in disability (Subject to change time to time as per relevant rules) or Rs. 10 Lacs in case of deach of the employee (Subject to change time to or Rs. 10 Lacs in case of deach of the employee (Subject to change time to or Rs. 10 Lacs in case of deach of the employee (Subject to change time to time as per relevant rules).
12. **Earnest money :-** Earnest money of Rs. 3000/- has to be deposited in the form of Demand Draft in favour of R.A.O.MPPTCL, Indore.
13. **Security Deposite :-** Security Deposite of 10% as to be deposited if your order is placed / deducted from your bill.
14. **Quantity of work can be increased or decreased as per the requirement of order date.**

Thanking you.

Yours faithfully


E.E. (TESTING)
MPPTCL UJJAIN